TELANGANA HOUSING CORPORATION LIMITED

H.No.3-6-184,street no.17, Urdugally lane, Himayathnagar, Hyderabad-29

From
V.P.Gautham, IAS
Managing Director

To
All the District Collectors in the State

Cir. No.3882 /TGHCL / INDIRAMMA INDLU/Monitoring/2025, Dt.16/6/2025.

Sub: TGHCL – Indiramma Indlu – Grounding of houses – Photo capture in Mobile App – Improper photo documentation by Panchayat Secretaries - instructions – Technical checklist for AEs – communicated - Reg.

Ref: 1. G.O.Rt.no.259, TR&B (RH&c.A1) dept
2. Online stage approval report.

***

It is hereby informed that the execution of the INDIRAMMA INDLU Housing Programme is being closely monitored through the online portal. The workflow begins with markout photo capture by the Panchayat Secretary/Ward Officer at the respective site.

Upon completion of the basement stage and capture of corresponding photos, the first installment (basement bill payment) is processed upon approval by AE/DEE/PD/Collector and validated by AI verification. The AI system evaluates the stage completion indicated vis-à-vis the submitted photos.

Numerous payments have been withheld at the basement stage due to AI disapproval, causing repeated grievances from beneficiaries. Upon verification, the following issues were observed in the uploaded photos:

Dont's

1. Improper photos capturing only part of the basement.
2. Certifying stage completion before laying internal plinth beams.
3. Incomplete CRS masonry
4. Basements laid only for Single room/two rooms, not adhering to approved plan (minimum one hall, one bedroom, one kitchen and toilet).
5. Taking photo after the Basement is completely covered by mud/gravel, making it impossible to view the basement/ plinth beams.

(A soft copy of AI-rejected cases is emailed separately with this circular.)

Do's

1. Panchayat Secretary/Ward Officer to capture basement stage completion as follows:

    - All internal walls are completed
    - Minimum plinth height of 45 cm above ground
    - Plinth beam is laid (for short column structures)
    - Capture basement stage photos before filling with gravel.
    - After opening the Mobile App for capturing the geo-coordinates, wait for 2 minutes for stabilization of the device to capture appropriate location details.
    - Must motivate beneficiaries to strictly follow the approved plan of two rooms, kitchen and toilet, with plinth area between 400 to 600 sq.ft.
    - Must capture photos from 3 angles: front, side, and top

2. Assistant Engineer (AE):
    - Visit and guide these activities - Pre-excavation, post-excavation, levelling, short column/RR masonry, plinth beam, brick masonry, lintel, slab centring, reinforcement, slab laying, plastering, flooring, plumbing, etc.
    - To conduct frequent instructions at each stage of construction.
    - Must fill and attest the checklist (enclosed; to be integrated into the online portal by CGG in due course)
3. Deputy Executive Engineer (DEE) & Project Director (PD):
    - Must perform desk verification and adhere to above protocols prior to approval.

All District Collectors are requested to issue clear instructions to field staff to ensure accurate photo documentation and compliance with these guidelines so as to ensure smooth release of payments.

Sd/- 16.6.2025
MANAGING DIRECTOR

Encl: Check list by the AE

Copy to all the Project Director(H) in the State for necessary action.

//Attested//

Executive Engineer