TELANGANA HOUSING CORPORATION LIMITED H.NO.3-6-184, STREET NO 17, HIMAYATNAGAR HYDERABAD

CIRCULAR

Circular No: 834086 / TGHCL-ENGG/ Role & Duties / AEs /22/2025
Engg-Section 04-10-2025

Sub: INDIRAMMA INDLU – Circular Instructions to AEs to strictly adhere to field duties during village inspections and motivate non-started beneficiaries – Reg.

Ref: 1. Circular No: 834086 / TGHCL-ENGG/ Role & Duties / AEs /22/2025 Engg-Section 10/08/2025 of MD, TGHCL, Hyd.
2. G.O Rt No.259 of TR&B (RH&C.A1) Dept., dt: 03.06.2025

*****

In the references 1st and 2nd cited, the roles and responsibilities of Assistant Engineers have been communicated for implementation of the Indiramma Indlu programme. However, it has come to the notice of the undersigned that several Assistant Engineers (AEs) during their village visits are limiting their inspections just to verification of stage-wise photographs captured by Panchayat Secretaries and leaving verification of left over stage completed houses which are not captured by Panchayat Secretaries, without conducting physical verification of site conditions, material usage, or interaction with beneficiaries.

This approach is strictly against the guidelines issued under the Indiramma Indlu programme and undermines the key objectives of ensuring construction quality, material accountability, and beneficiary engagement.

In this context, the following mandatory instructions are reiterated for strict compliance:

1. Field Visit & Physical Inspection:

- AEs shall personally inspect each ongoing construction site during their village visits.
- They must verify the actual physical progress of the house, and avoid depending only on photographs
- The inspection shall include assessment of material quality, workmanship, adherence to plinth area norms, and verification of each construction stage .

2. Interaction with Beneficiaries and Masons:

- AEs shall interact with the beneficiary and the mason on-site to verify any issues in construction, funding, or material availability.
- Ensure that the material estimate sheet has been shared and followed by the beneficiary.

3. Identification & Motivation of Non-Starters

- AEs shall identify all houses where construction has not yet commenced and record reasons for delay, such as:
  - Land/site issues
  - Material shortage
  - Non-availability of masons/labour
  - Financial or personal constraints
- AEs must actively counsel and motivate such beneficiaries to begin construction at the earliest. Wherever required, they shall provide technical guidance, coordinate with masons, and advise on material procurement to ensure the beneficiaries feel fully supported.

4. Documentation & Reporting:

- AEs shall maintain village-wise inspection registers clearly noting:
  1. Name of beneficiary
  2. Stage of construction verified or not started
  3. Reasons for delay (if any)
  4. Remarks on quality and material
  5. Name of mason
  6. Any deviations noticed
  7. Technology adopted at different stages of construction
  8. Record of various material suppliers operating in the Mandal
- Reports must be submitted weekly to the Deputy Executive Engineer (DEE) concerned.

5. Guidance to beneficiaries about projections at SLAB LEVEL:

It has been observed from field photographs that in some cases, slab projections exceed 3 feet. Such deviations may:

- Lead to a substantial increase in construction cost,

- Raise eligibility concerns under the BPL category, and
- Expose beneficiaries to debt burden, thereby defeating the core objective of the scheme.

AEs must guide beneficiaries appropriately to avoid such deviations.

6. Strict Action for Non-Compliance:

- Any lapse, negligence, or casual approach in conducting inspections will be viewed with utmost seriousness.
- Disciplinary proceedings shall be initiated against Assistant Engineers who fail to carry out mandatory physical verifications or submit incomplete / misleading reports.

All Assistant Engineers are hereby directed to treat these instructions with utmost seriousness and ensure that village visits are purposeful, accountable, and strictly in adherence to the quality standards of the Indiramma Indlu programme.

04-10-2025

CHIEF ENGINEER

To
All Assistant Engineers
TGHCL
Copy to all the District Collectors for information
Copy to all the Project Directors, TGHCI, for infromation
Copy General Manager (Admn) for infromation

// Attested //

Executive Engineer
Telangana Housing Corporation Ltd.
Hyderabad-500029.

Digitally signed by
CHAITANYA KUMAR MUDAVATH
Date: 04-10-2025 17:02:45