# PROJECT SETTINGS

| | | |
|---|---|---|
| Project Name | : | G+2 RB PLINTH BEAM DESIGN |
| Client Name | : | Unassigned |
| Engineer Name | : | Unassigned |
| Design File | : | E:\MY PROJECT 4-1\STAAD\RCDC FILES\G+2 Project Plan-Beam-1-1.981 m.R1.rcdx |
| Analysis File | : | E:\MY PROJECT 4-1\STAAD\G+2 Project Plan.std |
| Analysis Last Modified | : | 06-10-2026 03:00:45 |

## General and Reinforcement Settings

### Material Properties

| | | | |
|---|---|---|---|
| Concrete Grade | : | M25 | N/sqmm |
| Steel Grade (Main) | : | Fe550 | N/sqmm |
| Steel Grade (Shear) | : | Fe550 | N/sqmm |
| Top / Bottom Clear Cover | : | 30 | mm |
| Side Clear Cover | : | 30 | mm |
| Max Aggregate 2 Size | : | 25 | mm |
| Analysis Materials used | : | No | |

### Design Settings

| | | | |
|---|---|---|---|
| Ignore Torsion | : | Yes | |
| Value Less Than | : | 0.1 | kNm |
| Flange Beam Considered | : | None | |

### Rebar Selected

| | | |
|---|---|---|
| Rebar Used | : | 8,10,12,16,20,25,32,40 |

### Main Rebar

| | | |
|---|---|---|
| Minimum | : | 12 |
| Maximum | : | 20 |

### Shear diameter

| | | |
|---|---|---|
| Minimum | : | 8 |
| Maximum | : | 12 |

### SFR Rebar

| | | |
|---|---|---|
| Minimum | : | 8 |
| Maximum | : | 16 |

### Stirrup Spacing

| | | | |
|---|---|---|---|
| Minimum | : | 75 | mm |
| Maximum | : | 300 | mm |

| | | | |
|---|---|---|---|
| Spacing RoundOff | : | 5 | mm |

Percentage Reinforcement

| | | | |
|---|---|---|---|
| Minimum | : | 0.2 | % |
| Maximum | : | 4 | % |
| Nominal Reinforcement | : | 0.2 | % |

Detail Settings

| | | |
|---|---|---|
| Top Detailing Style | : | Best Fit |
| Bottom Detailing Style | : | Best Fit |

Crack Width Settings:

| | | |
|---|---|---|
| Crack Width IS 456 : 2000 + IS 13920 : 2016 Check | : | No |

**Curtailment Settings**

Top Reinforcement Curtailment Location

| | | | |
|---|---|---|---|
| End Support | : | L/4 | |
| Clear Cover | : | 30 | mm |
| Continuous Support | : | L/4 | |

Bottom Reinforcement Curtailment Location

| | | |
|---|---|---|
| Mid Span | : | L/6 |
| End Support | : | L/4 |
| Continuous Support | : | L/4 |

Ductile Beam

| | | |
|---|---|---|
| Factor of Depth | : | Dx2 |

Non Ductile Beam

| | | |
|---|---|---|
| Factor of Length | : | L/3 |
| Bending And Axial Force Design Settings | : | Not Consider |

**Beam Bar Spacing**

Skip maximum spacing criteria between rebar for zero bending moment : No

| Beam Width | Rebar Nos<=16 | Spacing | Rebar Nos>=20 | Spacing |
|---|---|---|---|---|
| 230 | 3 | 61 | 2 | 130 |